Lincoln-Lancaster County Health Department
Environmental Public Health Division
3140 N Street • Lincoln NE 68510-1514
Phone: 402-441-8643

A

Permit Number #500 1782

Onsite Wastewater Treatment System Permit Application

Include Form B and C. Submit correct fee with this Application

☑ Septic System ☐ Lagoon ☐ Other (Refer to Form C)

PLEASE PRINT OR TYPE

A. Onsite System Location

Address* TBD (no rural route) City Crete, NE Zip 68333

Legal Description 29 T8 R5 Principal meridian 7SE

1/4 1/4 Section Township Range Subdivison Addition Block Lot

PID _____ *Approx. Address (If to be determined) _____

B. Owner

Name Lucas Lingg Signature _____

Address 1412 Rodeo Rd City/State/Zip Crete, NE 68333

Home Phone 402-875-0218 Work Phone 402-826-7063

C. Certified Installer

Name: Troy Ross Signature _____

Address 2215 Lathrop Lake Cir City/State/Zip Crete NE 68333

Work Phone 402-610-1809

D. Engineer

☐ **Check and complete if engineer designed system** P.E. License Number: _____

Designer Name _____ Firm _____ Work Phone _____

E. This system will serve a

☑ Residential Dwelling Number of Bedrooms 4 Whirlpool Bathtub? ☐ Yes ☑ No Total Acres 5

Garbage Grinder? ☑ Yes ☐ No

☐ Commercial Establishment/Other Facility Specify _____ Design flow in gallons per day _____

Type of Wastewater ☐ Domestic ☐ Non-Domestic

DO NOT WRITE BELOW THIS LINE

Approval Process

1. Health Department

Site visits _____ Date rec'd _____ **ACTION** ☐ Approved ☐ Disapproved

Date frwd _____ Signature _____

Comments _____

2. Supt. Bldg. Insp. or Village Clerk

Comments _____ Date rec'd _____ **ACTION** ☐ Approved ☐ Disapproved

Date frwd _____ Signature _____

3. City or County Engineer

Comments _____ Date rec'd _____ **ACTION** ☐ Approved ☐ Disapproved

Date frwd _____ Signature _____

Installation Final Written Approval

By _____

Date _____

Business Office Use Only
Date Received 12-18-18 Amount Paid $420.00
Received By JKO Cash/Check No. C2500

White - Health Department Yellow - Engineer Pink - Building & Safety

Onsite Wastewater Treatment System
Soil Percolation Test Data Sheet

Nebraska DEQ

Owner Name Lucas Gingg Phone 402-875-0218

Address 1412 Rodeo Rd Crete NE 68333
City State Zip

Location (Attach a sketch of the property showing test hole locations)

__ __ 29 T8 R5 Lancaster
¼ ¼ Section Township Range County

Lot # 7SE Subdivision Principal Meridian

Soil Type (Check one)

Sand ____ Silt ____ Clay ____ Sandy Clay ____ Loamy Sand ____ Silty Clay ____

Silty Clay Loam ✓ Sandy Loam ____ Silt Loam ____

Dates of Test

Start Date 11-19 to End Date 11-20, 20 18

Weather Conditions

Precipitation -0- Avg. Temp 35 °F

Percolation Test Measurements and Data

Hole No.	Hole Depth (in.)	Pre-saturation Period: Start Date (Mo./Day)	Pre-saturation Period: Start Time (Hr./Min)	Pre-saturation Period: End Date (Mo./Day)	Pre-saturation Period: End Time (Hr./Min)	Percolation Readings (last period): Start Date (Mo./Day)	Percolation Readings (last period): Start Time (Hr./Min)	Percolation Readings (last period): Start Water Level (inch)	Percolation Readings (last period): End Time (Hr./Min)	Percolation Readings (last period): End Water Level Drop (inch)	Results: Elapsed Time (minutes)	Results: Drop in Water Level (inches)	Results: Percolation Rate (m ÷ l) (Minutes per inch)
1	30"	11-19	6PM	11-20	6PM	11-20	6PM	20	6:30	19	30	1	30
2	"	"	"	"	"	"	"	"	"	19	"	1	30
3	"	"	"	"	"	"	"	"	"	18½	"	1.5	20

Tests must be performed by a certified professional, a professional engineer or a registered environmental health specialist.

Signature

Certificate or License # 2705

Address 2215 Cottonwood Lake Cir.

City Crete St. NE Zip 68333

Phone 402-610-1304

Sum of Percolation Rates = 80

Avg. of Percolation Rates* = (sum of rates ÷ number of tests) (minutes per inch) 27

* If rates vary by more than 20 min/in., do not average. Use slowest rate measured for sizing soil absorption area.

Lincoln-Lancaster County Health Department
Environmental Public Health Division (402) 441-8027
3131 O Street Lincoln, Nebraska 68510-1514

ON-SITE WASTE WATER SYSTEM
CONSTRUCTION - INSTALLATION PERMIT
No. HS001782

System Type: Standard

Situs: No Site Address Specified

Issued: 4/12/2019

Expires: 4/12/2020

Description:

Owner:

Shavonna M. Lausterer, MPH, CPH, Health Director

Dear Applicant:

The above document is your permit to construct a new On-site Waste Water System at the location listed. Please contact this office once the sytem is complete in order to schedule a final inspection before use.

Shavonna M. Lausterer, MPH, CPH
Health Director

TROY ROSS
2215 LOTHROP LAKE CIR
CRETE, NE 68333

Lincoln-Lancaster County Health Department
Environmental Public Health Division
3140 N Street • Lincoln NE 68510-1514
Phone: 402-441-8643

STANDARD

A

Permit Number #500 1782

Onsite Wastewater Treatment System Permit Application

Include Form B and C. Submit correct fee with this Application

☑ Septic System ☐ Lagoon ☐ Other (Refer to Form C)

PLEASE PRINT OR TYPE

A. Onsite System Location 11966 W Sprague Rd

Address* TBD (no rural route) City Crete, NE Zip 68333

Legal Description 29 T8 R5 Principal meridian 7SE

02-29-401-001-000 Section Township Range Subdivison Addition Block Lot

PID 0229401000 *Approx. Address (If to be determined)

B. Owner

Name Lucas Lingg Signature

Address 1412 Rodeo Rd City/State/Zip Crete, NE 68333

Home Phone 402-875-0218 Work Phone 402-826-7063

C. Certified Installer

Name: Troy Ross Signature

Address 2215 Lathrop Lake Cir City/State/Zip Crete NE 68333

Work Phone 402-610-1809

D. Engineer ☐ **Check and complete if engineer designed system** P.E. License Number:

Designer Name Firm Work Phone

E. This system will serve a

☑ Residential Dwelling Number of Bedrooms 4 Whirlpool Bathtub? ☐ Yes ☑ No Garbage Grinder? ☑ Yes ☐ No Total Acres 38.66 5

☐ Commercial Establishment/Other Facility Specify Design flow in gallons per day

Type of Wastewater ☐ Domestic ☐ Non-Domestic

DO NOT WRITE BELOW THIS LINE

Approval Process

1. Health Department
Site visits 06/2019 exact date unknown D.C
Comments
Date rec'd
Date frwd
ACTION ☐ Approved ☐ Disapproved
Signature

2. Supt. Bldg. Insp. or Village Clerk
Comments
Date rec'd
Date frwd
ACTION ☐ Approved ☐ Disapproved
Signature

3. City or County Engineer
Comments
Date rec'd
Date frwd
ACTION ☐ Approved ☐ Disapproved
Signature

Installation Final Written Approval
By
Date 8/13/19

Business Office Use Only
Date Received 12-18-18 Amount Paid $420.00
Received By Cash/Check No 2500

White - Health Department Yellow - Engineer Pink - Building & Safety

Form A Updated: 4/15

Lancaster County Health Department
Environmental Public Health Division
3140 N Street • Lincoln NE 68510-1514
Phone: 402-441-8643

4

Exhibit 5

Permit Number: HS 001782

Onsite Wastewater Treatment System

Inspection Sheet

Date ~~8~~ 8/13/19 Legal Description ¼ ¼ 29/8/5 Section/Township/Range 7SE

Onsite System Location

Address (no rural route) 11966 W Sprague RD. City

Owner Address

Mark One: ~~☐~~ Dwelling ☐ Non-dwelling

~~☐~~ New System ☐ Alteration [☐ Tank Only ☐ Trench Only] ☐ Lateral Only

☐ Temporary modification (Describe problem causing discharge and reason for temporary modification):

Drainfield Absorption System:

~~☐~~ Lateral ☐ Bed ☐ Non-standard (engineer-designed and NDEQ approved) ☐ Holding Tank ☐ Trench

Total square feet of drainfield 1,080 Sq. Ft. Tank Size 1,500 gals

Total length of laterals 240' Type of Distribution: ☐ Chamber ☐ Perforated Pipe ☐ ~~Other~~ (describe) EZ Flow

No. of Absorption Laterals 3 Width 4.5 Factor No. of Drop Boxes Distribution Box 1

Leveling Method Used Laser

Setbacks (Check the Boxes Below if the Required Setback has been Satisfied):

Distance From:	Private Well	Public Well	Surface Water	Ground water	Pressure Water Lines	Property Lines
Tank (ft)	50 ☐	500 ☐	50 ☐	NA ☐	10 ☐	5 ☐
Field (ft)	100 ☐	500 ☐	50 ☐	4 ☐	25 ☐	5 ☐

Geographical Coordinates to 6 Decimals:

Tank

Lateral #1 N/A Lateral #3

Lateral #2 Lateral #4

Comments:

Inspections prior to Final Approval
Initial DG Date June Unknown

Follow-Up Date

Follow-Up Date

Installation Final Written Approval
By Doug Thiele

Date 8/13/19

Field Note Drawing (See Reverse Side):

Updated 4/15

Lincoln-Lancaster County Health Department
Environmental Public Health Division
3140 "N" Street • Lincoln, NE 68510-1514
Phone: 402-441-8022

AUG 07 2019

D

Permit Number:

Onsite Wastewater Treatment System

As-Built Description and Drawing

Type of Onsite Wastewater System: Lagoon (Skip to Back Page) (Subsurface Septic) Mound

Onsite Wastewater System Location Sec 29 Town T8 Range R5

Address or Legal Description or Parcel Identification Number (PID) _____

Owner Lucas Lingg Address 11966 W Sprague Rd. Crete

A. Wastewater Piping

1. Material: PVC Diameter: 4" in.
2. Distance between dwelling and septic tank: 9 ft.

B. Septic Tank

1. Material: Plastic
2. Capacity: 1500 gal.
3. Depth to top of tank, below unfinished grade: 15 in.
4. Distance to:
   - Well 130 ft.
   - Pressure line 60 ft.
   - Property line 350 ft.
   - Foundation 9 ft

C. Distribution Box or Drop Box

Distance **and** Direction from septic tank: N. ft. 29

D. Drainfield/Absorption Field (circle one)

(Trench) Bed

1. Type: Perforated Pipe (Chamberless) Other

Material brand and inside width of Chamberless:
EZ Flow

2. Number of Laterals: 3
3. Length of each lateral (linear): ft. 80 ft. 80 ft. 80 ft. _____
4. Drainfield size: 1130 sq. ft.
5. Distance to:
   - Well 150 ft.
   - Pressure line 80 ft.
   - Property line 300 ft.
   - Depth of Groundwater 124

Was the Onsite Waste Water System covered prior to LLCHD inspection? YES (NO)

If Yes, the Certified Professional **must** sign below for final approval:

I swear and affirm that the system complies with Lincoln Municipal Code (LMC) 24.38 and/or County Resolution 02-0030 requirements and that the information and documentation submitted are true and accurate.

Certified Professional Signature _____ Date _____

Complete As-Built drawing on the back of this form.

N
19'
21'

Nate C. Hartman

From: Troy Ross <troy@rossplumbingco.com>
Sent: Friday, April 12, 2019 9:33 AM
To: Nate C. Hartman
Subject: FW: Ling
Attachments: Doc Apr 12, 2019, 0921.pdf

Nate

Please see attached drawing.

We are waiting on confirmation of the legal description but according to this it looks like it is Lot 1, Ling Landing Addition.

Thanks

Troy

Get Outlook for iOS

LINGG LANDING ADDITION

FINAL PLAT

SECTION TIES

South Quarter Corner Sec. 29 T8N R5E
Found 2" aluminum cap
NW 54.15' to 5/8" rebar
W 40.00' to capped rebar
SW 58.73' to 5/8" rebar

Southeast Corner Sec. 29 T8N R5E
Found 2" aluminum cap
NE 52.43' to 1/2" rebar
SE 49.57' to 1/2" rebar
SW 57.44' to 5/8" rebar

East Quarter Corner Sec. 29 T8N R5E
Found 2" aluminum cap
W 50.00' to 1" iron pipe
SE 53.11' to 5/8" rebar
E 50.01' to 1/2" rebar w/ cap

Center Sec. 29 T8N R5E
Found 1" Pipe (P165, AA 17134)
E 15.30' to nail in disk in the north face of gate post
W 6.96' to nail in disk in top of brace post
N 9.35' to nail in disk in the east face of gate post


West Sixteenth of the Southeast Quarter Sec. 29 T8N R5E
Set 5/8"X24" rebar w/ LS 695 cap
W 0.80' to fence North
NNE 1.63' to magnail in hedge post
N 1.50' to fence East

Center of the Southeast Quarter Sec. 29 T8N R5E
Set 5/8"X24" rebar w/ LS 695cap
In line with fence East-West
WNW 1.76' to magnail in fence post
E 16.55' to magnail in fence post
W 50.00' to tree line South

South Sixteenth of the Southeast Quarter Sec 29 T8N R5E
Set Mag Nail in Asphalt Paving
N 50.01' to Capped Rebar
NE 51.71' to 5/8" Rebar
SE 49.03' to 5/8" Rebar

N

0 100' 200' 400'
SCALE: 1"=200'



CENTERLINE CURVE DATA						
CURVE #	RADIUS	ANGLE	TANGENT	LENGTH	CH DIST	CH BRG
C1	200.00'	65°37'30"	126.95'	229.07'	216.76'	N31°51'55"W
C3	400.00'	64°31'41"	252.52'	450.49'	427.06'	N32°24'50"W

LEGEND

◆ = FD. 2" ALUMINUM CAP
● = FD. 1" PIPE
△ = TEMPORARY POINT
○ = SET 5/8" x 24" REBAR W/ LS695 CAP
R1 = RECORDED DISTANCE (SURVEY BOOK P, PAGE 165)
M = MEASURED DISTANCE

Nate C. Hartman

From: Roger Bumgarner <roger@elementlincoln.com>
Sent: Wednesday, April 03, 2019 11:06 AM
To: Nate C. Hartman; troy@rossplumbingco.com
Cc: 'Andrey Kovaliv'
Subject: Lingg Residence
Attachments: 180273-FP-Sheet 1.pdf; 180273-FP-Sheet 2.pdf; 180273-FP-Sheet 3.pdf

Hi Nate,

Here is the new plat.

Troy – Can you get Nate the location of the septic? Then I think we'll be good to go.

Thank you both.

Roger Bumgarner
Element Homes LLC
402.580.7955
www.elementlincoln.com

Element
HOMES

From: Jill Schuerman <jschuerman@civildg.com>
Sent: Tuesday, April 2, 2019 1:30 PM
To: Amanda Lingg <amanda.preston@doane.edu>; Cassandra Litz <cassandra.litz@bhhsamb.com>
Cc: roger@ironwoodlincoln.com; Lucas Lingg <lucaslingg@gmail.com>
Subject: RE: Whoo! The plat is filed!

Roger can now get your building permit.

I am guessing your loan company will want you to close on your lot with your Grandma. To do that you can have an attorney create the deed or a title company. You will be closing on Lot 1, Lingg Landing Addition. If the title company or attorney has any questions just have them give me a call.

Jill D. Schuerman
Civil Design Group, Inc. & Allied Surveying & Mapping
8535 Executive Woods Drive
Suite 200
Lincoln, NE 68512
402-434-8494

From: Amanda Lingg <amanda.preston@doane.edu>
Sent: Tuesday, April 2, 2019 1:24 PM
To: Jill Schuerman <jschuerman@civildg.com>; Cassandra Litz <cassandra.litz@bhhsamb.com>
Cc: roger@ironwoodlincoln.com; Lucas Lingg <lucaslingg@gmail.com>
Subject: Re: Whoo! The plat is filed!

YEAH! i'm so excited :) thanks for letting us know Jill. What next steps do we need to do now?

Amanda Lingg

On Tue, Apr 2, 2019 at 1:07 PM Jill Schuerman <jschuerman@civildg.com> wrote:

This final plat has been recorded at Register of Deeds. #2019010458. Fee $58.00

Roger – It will take a day or two for the plat to be able to be printed from the Register of Deeds. Let me know if Bldg & Safety gives you issues and I will get you a filed copy. You can also have Bldg & Safety talk to Tom at Planning also.

Jill D. Schuerman

Civil Design Group, Inc. & Allied Surveying & Mapping

8535 Executive Woods Drive

Suite 200

Lincoln, NE 68512

402-434-8494

LINGG LANDING ADDITION

FINAL PLAT

SURVEYOR'S CERTIFICATE

I hereby certify that I have caused to be surveyed the Subdivision to be known as Lingg Landing Addition. A subdivision of Lot 7 Irregular Tracts, located in the Southeast Quarter of Section 29, Township 8 North, Range 5 East, of the 6th P.M., Lancaster County, Nebraska and more particularly described as follows:

Referring to the Southwest Corner of the Southeast Quarter of Section 29, thence Northerly on the West Line of the Southeast Quarter of Section 29 on an assumed bearing of N 00°09'00" W for a distance of 40.01' to the Southwest Corner of Lot 7 Irregular Tracts said point being on the North 40.00' Right-of-way Line of W. Sprague Rd., said point also being the Point of Beginning;

Thence N 00°09'00" W on the West Line of Lot 7 Irregular Tracts and the West Line of the Southeast Quarter of Section 29 for a distance of 1275.66' to the Northwest Corner of said Lot 7; Thence S 89°12'19" E on the North Line of Lot 7 Irregular Tracts for a distance of 1317.19' to the Northeast Corner of said Lot 7; Thence S 00°15'40" E on the East Line of Lot 7 Irregular Tracts for a distance of 1279.22' to the Southeast Corner of said Lot 7, said point also being on the North 40.00' Right-of-way Line of W. Sprague Rd.; Thence N 89°03'10" W on the South Line of Lot 7 Irregular Tracts and the North 40.00' Right-of-way Line of W. Sprague Rd. for a distance of 1319.74' to the Point of Beginning, and having a calculated area of 38.56 acres more or less.

Subject to any and all easements and restrictions of record.

Permanent monuments have been placed at all lot corners, street intersections, points of curvature, centerline points of tangency, and at all other points required by the Lancaster County, Nebraska, Land Subdivision Resolution.

All dimensions are chord measurements unless shown otherwise, and are in feet or decimals of a foot.

Signed this ___ day of _____, 20___.

_____

Marc J. Raphael #695
Allied Surveying & Mapping, Inc.
8535 Executive Woods Drive, Suite 200
Lincoln, NE 68512
Ph. (402)434-2686

DEDICATION

The foregoing plat, known as Lingg Landing Addition, as described in the surveyor's certificate is made with the free consent and in accordance with the desires of the undersigned, the sole owners, and the easements shown thereon are hereby granted in perpetuity to the LANCASTER COUNTY, NEBRASKA, Windstream Nebraska Inc., Time Warner Cable Midwest LLC, Black Hills Energy, and Norris Public Power District, their successors, permittees, and assigns, to allow entry for the purpose of construction, reconstruction, repair, operation and maintenance of wires, cables, conduits, fixtures, poles, towers, pipes, and equipment for the distribution of electricity and gas; telephone and cable television; wastewater collectors; storm drains; water mains and all appurtenances thereto, over, upon, or under the easements as shown on the foregoing plat.

The construction or location of any building or structure, excluding fences, over, upon, or under any easement shown thereon shall be prohibited. Lancaster County its successors, permittees, and assigns are hereby held harmless for the cost of replacement or damage to any improvement or vegetation over, upon, or under any easement shown thereon.

The construction or location of any fence or other improvement which obstructs drainage shall be prohibited over, upon, or under any drainage easement shown hereon.

The right of direct vehicular access to West Sprague Road is hereby relinquished except at the 60' wide Public Access Easement, maintenance, utility and drainage easement shown hereon.

The public access, maintenance and utility easement shown hereon shall be for public access and the public is hereby granted the right of such use. All lots and outlots with access to this easement are hereby granted the right to maintain, repair, or rebuild the driveway within this access easement as necessary.

The 10.00' of additional road right-of-way shown hereon along West Sprague Road is hereby dedicated to the public.

The natural drainage shall be maintained across the 60' Public Access and Utility easement.

WITNESS MY HAND:

_____

Viola Preston, Trustee
Preston Family Trust

ACKNOWLEDGMENT

STATE OF _____)
) SS
_____ COUNTY)

On this ___ day of _____, 20___, before me, the undersigned, a notary public, duly commissioned, qualified for and residing in said county, personally came Viola Preston, Trustee, Preston Family Trust, to me personally known to be the identical person whose name is affixed to the dedication of the foregoing plat and she acknowledged the same to be her voluntary act and deed and the voluntary act and deed of said company.

_____

NOTARY PUBLIC

My commission expires the ___ day of _____, 20___.

PLANNING DIRECTOR'S APPROVAL

The Planning Director, Section 3.16 of the Lancaster County Land Subdivision Regulations, hereby approves this Final Plat.

_____ _____

Planning Director Date

LINGG LANDING ADDITION

FINAL PLAT

LIEN HOLDER CONSENT AND SUBORDINATION

The undersigned, holder of that certain lien against real property described in the plat known as "Lingg Landing Addition", said lien being recorded in the Office of Register of Deeds of Lancaster County, Nebraska, as Instrument Numbers 2019001618 and 2019001619, does hereby consent to the dedication of and subordinate the Lien to any utility (sewer, water, electric, cable TV, telephone, natural gas) easements, or streets, or roads, pedestrian way easements, and access easements and relinquishments of access, dedicated to the public, all as shown on the Plat, but not otherwise. The undersigned confirms that it is the holder of the Lien and has not assigned the Lien to any other person.

West Gate Bank
Trustee and Beneficiary

By:_____, _____
Name Title

ACKNOWLEDGMENT

STATE OF NEBRASKA)
) SS
_____ COUNTY)

The foregoing instrument was acknowledged before me this ___ day of

_____, 20___, by _____,
Name
_____ on behalf of said West Gate Bank.
Title Company

_____
NOTARY PUBLIC

My commission expires the ___ day of _____, 20____.

LINGG LANDING ADDITION

FINAL PLAT

SECTION TIES

South Quarter Corner Sec. 29 T8N R5E
Found 2" aluminum cap
NW 54.15' to 5/8" rebar
N 40.00' to capped rebar
SW 58.73' to 5/8" rebar

Southeast Corner Sec. 29 T8N R5E
Found 2" aluminum cap
NE 52.43' to 1/2" rebar
SE 48.57' to 1/2" rebar
SW 57.44' to 5/8" rebar

East Quarter Corner Sec. 29 T8N R5E
Found 2" aluminum cap
W 50.00' to 1" iron pipe
SE 53.11' to 5/8" rebar
E 50.01' to 1/2" rebar w/ cap

Center Sec. 29 T8N R5E
Found 1" Pipe (P165, AA 17134)
E 15.30' to nail in disk in the north face of gate post
W 6.96' to nail in disk in top of brace post
N 9.35' to nail in disk in the east face of gate post

West Sixteenth of the Southeast Quarter Sec. 29 T8N R5E
Set 5/8"X24" rebar w/ LS 695 cap
W 0.80' to fence North
NNE 1.63' to magnail in hedge post
N 1.50' to fence East


Center of the Southeast Quarter Sec. 29 T8N R5E
Set 5/8"X24" rebar w/ LS 695cap
In line with fence East-West
WNW 1.76' to magnail in fence post
E 16.55' to magnail in fence post
W 50.00' to tree line South

South Sixteenth of the Southeast Quarter Sec 29 T8N R5E
Set Mag Nail in Asphalt Paving
N 50.01' to Capped Rebar
NE 51.71' to 5/8" Rebar
SE 49.03' to 5/8" Rebar

N

0 100' 200' 400'

SCALE: 1"=200'



CENTERLINE CURVE DATA						
CURVE #	RADIUS	ANGLE	TANGENT	LENGTH	CH DIST	CH BRG
C1	200.00'	65°37'30"	128.95'	229.07'	216.76'	N31°51'55"W
C3	400.00'	64°31'41"	252.52'	450.49'	427.06'	N32°24'50"W

LEGEND

- ⊕ = FD. 2" ALUMINUM CAP
- ● = FD. 1" PIPE
- △ = TEMPORARY POINT
- O = SET 5/8" x 24" REBAR W/ LS695 CAP
- R1 = RECORDED DISTANCE (SURVEY BOOK P, PAGE 165)
- M = MEASURED DISTANCE

SCANNED

AUG 07 2019

D

Lincoln-Lancaster County Health Department
Environmental Public Health Division
3140 "N" Street • Lincoln, NE 68510-1514
Phone: 402-441-8022

Permit Number:

Onsite Wastewater Treatment System

As-Built Description and Drawing

Type of Onsite Wastewater System: Lagoon (Skip to Back Page) (Subsurface Septic) Mound

Onsite Wastewater System Location

sec 29 Town T8 Range R5

Address or Legal Description or Parcel Identification Number (PID) _____

Owner Lucas Lingg Address 11966 W Sprague Rd. Crete

A. Wastewater Piping

1. Material: PVC Diameter: 4" in.
2. Distance between dwelling and septic tank: 9 ft.

B. Septic Tank

1. Material: Plastic
2. Capacity: 1500 gal.
3. Depth to top of tank, below unfinished grade: 15 in.
4. Distance to:
   - Well 130 ft.
   - Pressure line 60 ft.
   - Property line 350 ft.
   - Foundation 9 ft

C. Distribution Box or Drop Box

Distance **and** Direction from septic tank: N. ft. 29

D. Drainfield/Absorption Field (circle one)

(Trench) Bed

1. Type: Perforated Pipe (Chamberless) Other

Material brand and inside width of Chamberless:
EZ Flow

2. Number of Laterals: 3
3. Length of each lateral (linear): ft. 80 ft. 80 ft. 80 ft. _____
4. Drainfield size: 1130 sq. ft.
5. Distance to:
   - Well 150 ft.
   - Pressure line 80 ft.
   - Property line 300 ft.
   - Depth of Groundwater 124

Was the Onsite Waste Water System covered prior to LLCHD inspection? YES (NO)

If Yes, the Certified Professional **must** sign below for final approval:

I swear and affirm that the system complies with Lincoln Municipal Code (LMC) 24.38 and/or County Resolution 02-0030 requirements and that the information and documentation submitted are true and accurate.

Certified Professional Signature _____ Date _____

Complete As-Built drawing on the back of this form.

N
13'
11'
21'
9'
19'
7'6"
80'
80'
80'