LINCOLN-LANCASTER COUNTY HEALTH DEPARTMENT

ENVIRONMENTAL HEALTH DIVISION

2200 St. Marys Ave Lincoln, NE 68502-3785 (402) 441-8000

NON TRANSFERABLE

PERMIT

Permit
SEWAGE INSTALLATION

No. 93380096901

Issued 03/25/93
Expires 09/25/93
Revenue Code 18754

Establishment
JOHN BECK
T10N R7E SEC 13
LOT 15

FEES: $150.00

TOTAL $150.00

Permittee
JOHN BECK
1100 S 30 ST
LINCOLN NE 68510

Issued By M. Jane Ford
Health Director

THIS LICENSE OR PERMIT IS ISSUED SUBJECT TO REVOCATION AS PROVIDED BY LAW
"POST IN A PROMINENT PLACE"

FORM 20103-0477
REQUEST FOR SITE CLEARANCE AND PERMIT
FOR INDIVIDUAL SEWAGE DISPOSAL SYSTEM
City Ordinance No. 9150 ☒
County Resolution No. 2832 ☒

LINCOLN-LANCASTER COUNTY HEALTH DEPARTMENT
Division of Environmental Health
2200 St. Marys Avenue
Lincoln, Nebraska 68502
Phone: 471-7800

A

FILING FEE: $150.00

FILE NO. _____

DATE: _____

The undersigned hereby requests SITE CLEARANCE and PERMIT to construct an Individual Sewage Disposal System in conformance with appropriate resolution or ordinance, as described herein:

1. Legal description of property: Twp. 10N ; Range 7E ; Section 13 ;
   Block _____ : Lot 15 IT : Addition S½ of SW¼
   Street Address 10100 HOLDREGE

2. Property Use: Residential ☒ ; Commercial ☐ Other Use ☐
   No. of Bedrooms 3 . Describe _____

3. Type of Individual Sewage Disposal System: Septic Tank ☒ ; Other ☐

4. Distance to public sewer: _____ ft.

John Ed
Signature of Applicant (Owner or Lessee)

1100 S. 30th Lincoln
Address

68510

(Do not write below this double line)

1. Health Department: Date Rec'd. 3/25/93. Date Frwd. 3/25/93. ACTION: Approved ☒ Disapproved ☐ Signature: Jerrold C. Hood
2. Supt. Bldg. Insp.: or Village Clerk Date Rec'd. 3/25/93. Date Frwd. 3/25/93. ACTION: Approved ☒ Disapproved ☐ Signature: _____
3. City or County Engineer : Date Rec'd. 3-25-93. Date Frwd. 3-25-93. ACTION: Approved ☒ Disapproved ☐ Signature: _____

REMARKS OR REASONS FOR DISAPPROVAL _____

Site Visits:
Date: 11-5-93 by: _____
Date: _____ by: _____
Date: _____ by: _____

INSTALLATION FINAL WRITTEN APPROVAL
Date: 11-18-93 By: _____

White: Health Dept. Copy
Yellow: Engineers Copy
Pink: Bldg. Inspector's Copy

FORM 23-43

FORM 20105-0477
SOIL ABSORPTION TEST DATA REPORT
(Annex to Application)
(Reference: City Ordinance No. 9150 and County Resolution No. 2832)

LINCOLN-LANCASTER COUNTY HEALTH DEPARTMENT
Division of Environmental Health
2200 St. Marys Avenue
Lincoln, Nebraska 68502
Phone: 471-7800

B

FILE NO. _____

PROPERTY WHERE SOIL TESTED:

Location: Township _____; Range _____; Section & ¼ Section _____.
Property Dimensions: _____ ft. x _____ ft. Area: _____ acres. (Attach Sheet C with sketch of property).
Soil Type: Silty Clay ☐ ; Silty Clay Loam ☐ ; Sandy Loam ☐ ; Silt Loam ☐ ; Clay Loam ■ .
Dates of Tests: 5-21-87 to 5-22-87. Weather: Precip. 0 Temp. 65°.
Hole's-3- had water in From Pre-Test
OWNER: John R. Beck
Test Taking At 98th & Holdrege 1000 Feet East N. Side
Address: 1100 S. 30th Lincoln NE. 68510

PERCOLATION TEST DATA TABLE

a.	b.	c.	d.	e.	f.	g.	h.	i.	j.	k.	l.	m.	n.
		Pre-Saturation Period				Percolation Readings						Results	
		Start		End		Start			End				
Hold No.	Hole Depth (in.)	Date (Mo./ Day)	Time (Hr./ Min.)	Date (Mo./ Day)	Time (Hr./ Min.)	Date (Mo./ Day)	Time (Hr./ Min.)	Water Level (in.)	Time (Hr./ Day)	Water Level (in.)	Elapsed Time (Min.)	Water Level Drop (in.)	Percolation Rates (Min./in.)
1	36"	5-21	5:30 pm	5-22	4:30 pm	5-22	4:30 pm	6"	8:30 pm	5¼"	30m	¾"	
2	36"	5-21	5:30 pm	5-22	4:30 pm	5-22	4:30 pm	6"	8:30 pm	5"	30m	1"	
3	36"	5-21	5:30 pm	5-22	4:30 pm	5-22	4:30 pm	6"	8:30 pm	5¾"	30m	¼"	
4	36"	5-21	5:30 pm	5-22	4:30 pm	5-22	4:30 pm	6"	8:30 pm	5½"	30m	½"	
5	36"	5-21	5:30 pm	5-22	4:30 pm	5-22	4:30 pm	6"	8:30 pm	5¼"	30m	¾"	
6	36"	5-21	5:30 pm	5-22	4:30 pm	5-22	4:30 pm	6"	8:30 pm	5¼"	30m	¾"	

Mike Woodland
Signature of Person Conducting Test
Address 2525 Cleveland Phone 464-0638

Sum of Percolation Rates: _____
Average of Rates: _____
Mean of Rates: _____

(Do not write below this line)


REVIEWING ACTION

Remarks: _____
Soil Type (SCS): Wymore Silty Clay Loam
Date: May 29, 1987

Approved Percolation Rate (a)
A. 44 min./inch
B. _____ min./inch
C. _____ min./inch

Jerrold C. Hood
Signature of Reviewing Official

893 ft²
3ft 298
4ft 223


S 89 55 15" E
N 0 25 W
LOT 15 S. 1/2 of S.W. 1/2
13-10-7
ZONED AGR
MINIMUM SIDE SETBACK = 15'
MINIMUM FRONT SETBACK = 50'
Meter Mst
Elec. Service Entrance
Temp. Power
Transformer
Grade Reference
Septic Tank
Existing Driveway Entrance
S 90 00 00" E
HOLDREGE STREET
BECK RESIDENCE 10100 HOLDERGE
JOHN BECK 1100 S. 30th
LINCOLN, NE 68510 402 435-3918
PRELIM. SITE PLAN 3-5-93 1" = 80'

FORM 20104-0477
PLANS & SPECIFICATIONS FOR SEWAGE DISPOSAL SYSTEM (Annex to Application)
City Ordinance No. 9150 ☐
County Resolution No. 2832 ☐

LINCOLN-LANCASTER COUNTY HEALTH DEPARTMENT
Division of Environmental Health
2200 St. Marys Avenue
Lincoln, Nebraska 68502
Phone: 471-7800

D

DATE: _____

FILE NO. _____


SPECIFICATIONS AS BUILT

A. BUILDING SEWER:
1. Material _____; Diameter _____ in.
2. Distance above basement floor _____ in., or below basement floor _____ in.
3. Distance between dwelling and septic tank 52 ft.
4. Number of clean-outs 1.
5. Distances to:
Well or Suction Line 55 ft.; Stream _____ ft.; Pressure Line 20 ft.; Property Line _____ ft.


B. SEPTIC TANK:
1. Material CONCRETE; No. of compartments 1.
2. Capacity 1000 gals.;
3. Factory Built: Yes ☒ No ☐
(Company PRE-CAST)
4. Manholes: Over Inlet; diam. _____ in.
Over Outlet; diam. _____ in.
Riser Above ☒ Below ☐ Grade 2 in.
5. Inlet: Baffle ☐ ; or Tee ☐
6. Outlet: Baffle ☒ ; or Tee ☐
7. Depth of top of tank below finished grade 20 in.
8. Distances to:
Well or Suction Line 112 ft.; Stream _____ ft.; Pressure Line 72 ft.; Property Line 120 ft.

C. DISTRIBUTION BOX:
1. Material CONCRETE; Number - available outlets _____.
2. Factory Built: Yes ☒ No ☐
(Company _____)
3. Distance from Septic Tank 8 ft.

D. ABSORPTION FIELD: (Provide as built drawings on back of this form)
1. Type: Half Rounds ☒ Perforated Pipe ☐
Diameter of Half Round 20" or Perforated Pipe _____.
Material: fiberglass ☐ ; plastic ☐ ; concrete ☒ ; other _____.
2. Lateral Lines:
Number 3 ; Length of each line 100, 100, 24, _____, _____ ft.;
Total length of laterals 224 ft.;
Distance between lateral lines 17 ft.
3. Trench dimensions: Width 4 ft.;
Slope 0 in/100 ft.; Average Depth 33 in.
4. Filter Material: ROAD GRAVEL
Depth of Material 22 in.
5. Distances to:
Well or Suction Line 120 ft.; Stream _____ ft.; Pressure Line 90 ft.; Property Line 120? ft.



TYPICAL INDIVIDUAL SEWAGE SYSTEM DESIGN


N
WELL
30'
HOUSE
52'
SEPTIC TANK
8'
DIST. BOX
7'
100'
6.5'
24'
17'
100'
20'
3.5'
PROPERTY LINE